BUSINESS INTELLIGENCE FOR COST ANALYSIS IN CONSTRUCTION PROJECT

I Wayan Sugata ¹⁾ Agus Widodo ²⁾ INS Kumara ³⁾

^{1,2)} Magister Teknik Informatika Universitas Bina Nusantara

Jl. Merdeka 10, Jakarta 12020 Indonesia

email : sugataw@yahoo.com, ag45wd@binus.ac.id

³⁾ Teknik Elektro dan Komputer, Fakultas Teknik, Universitas Udayana, Bali

email: satya.kumara@unud.ac.id

ABSTRACT

Cost overrun in the field of project construction is still a global issue, and it is a challenge to seek for solution from various scientific discipline including information technology. This thesis aims to design a business intelligence application model for analyzing the cost of construction project to provide follow-up information as quickly and as early as possible to assist the executives to make valuable business decisions. This case study was prepared through literature reviews, interviews, and direct observation to obtain overview of the business processes in the construction company. The modeling of BI application which can be successfully developed using agile methods is very effective in addressing the change. This case study found that the application of business intelligence which provides information on key performance indicator (KPI) can assist the executives of the company to make decisions quickly and precisely, thus improving the performance of the project, especially in the cost control.

Key words

Business intelligence, cost control, construction project, key performance indicator, operational data

1. Introduction

The problem of cost overruns in the field of project construction is still a global issue in many countries especially in the development countries. According to [1], 90% of large construction projects MARA, Malaysia has experienced delays and cost-overruns since 1984. According to [2], United Kingdom, only 41% of respondents who have a project with cost-overruns less than 10%. According to [3], 53% respondents suffered one or more underperforming projects in 2014. For energy and natural resources and public sector respondents the figures were 71% and 90% respectively, only 31% of all respondent's projects came within 10% of budget in the past 3 years.

Many factors which cause cost overruns includes: weak management contractor, [4], inadequate controlling costs method [5], incorrect estimation techniques, inaccuracy estimation, [6], and the risks associated with complex and influence of lump-sum contract [7].

This study focuses more closely on the problem encountered in the construction project., such as addressing the difficulty in preparing complex report and data analysis required for evaluation in time, non-integrated database operational, inadequate management of project's and company's information.

The characteristic of the problem requires a system that could integrate project information, prepare report and analysis in time, managing company's information for reference to make better decision. This study proposed business intelligence as an appropriate method to address that problem.

2. Evolution of business intelligence in construction

In the 1990s and early 2000s [3] from IBM introduced the basic concept of the data warehouse to address various problems associated with business

processes and information architecture that define the flow of data from operational systems to decision support environments. Originally, operational systems were developed to support daily business operations by maintaining and updating databases for order entry, billing, accounting and payroll. They pointed out the limitations of operational systems for decision support and emphasized the need for more analytical information systems.

Later, researchers modified this concept into the modern data warehouse. [9], published the book “Building the Data Warehouse” to provide fundamental characteristics, designs, structures and other features of an effective data warehouse. He established a concrete definition of a data warehouse, which is most widely used in describing the basic features of data warehouses. [10], introduced the idea of online analytical processing (OLAP) to resolve problems that arise from the application of operational systems for decision support. OLAP is treated differently from online transaction processing (OLTP) with regard to the size, complexity, applicability, and time horizon of relevant data. Typically, OLTP focuses on day-to-day activities such as transactional entries which store specific values for individual fields. On the other hand, OLAP handles values which represent a historical view of the entity over an extended time horizon.

In the mid-2000s, application of data warehouses in the construction industry began to emerge. [11], investigated the application of the warehouse in construction management and developed a prototype Construction Management Decision Support System (CMDSS) to predict future inventory patterns and trends, with less query time. The CMDSS was used in the construction project of a student dormitory at Hong Kong Polytechnic University, resulting in the conclusion that the application of a data warehouse in construction management as a decision support system was promising because it allowed for multi-viewbased interactions between systems and users. [12], developed a prototype decision supporting system using data warehousing technique to determine the most appropriate site for residential house. By incorporating the GIS software and AHP tool into the system, the authors could consider the spatial and business factors for the decision making. [13], developed a Project-oriented Data Warehouse (PDW) for contractors using client-server architecture. They categorized construction data into four groups, including performance, materials, estimates, and bidding/contracts, with 16 dimension tables and ten fact tables. The PDW was reported to have properly captured the nature of the construction business, and it served as an efficient management tool for construction data obtained during the life cycle of the facility.

Furthermore, [14] examine the implementation of BI in TMSS (Traffic Management and Supervision System) is an integrated application for recording and

analysis of toll charges and provide evaluation results to the stakeholders, involving technology and modern platforms such as: Business Intelligence and Data Warehouse that is applied with Oracle Fusion Middleware technology platform and integrate data from various sources that the toll lanes, toll plazas, OBU (on Board Unit) and sales of CC (Company Card) points, banks, ERP, and others. Effects application of BI technologies inside TMSS mainly time efficiency in evaluating and analyzing the performance of business processes including reporting systems that provide high-level support for decision-making at all levels. [15], discussing the implementation of BI for monitoring the time and cost of the project based on the method of Earned Value Analysis (EVA) and underlines the predictive calculation of the project cost based on actual costs and revenues of the project.

3. Experimental Results

3.1 Multidimensional modeling for construction project data warehouse

One of the critical processes in designing a data warehouse is to determine what data should be extracted from the various data sources and loaded into the data warehouse. [13], introduced two strategies for the identification of project data sources: the need-based approach and the availability-based approach. In the availability-based approach, any data about operational systems that is currently available is selected and uploaded to the data warehouse. The need-based approach, investigate the potential need for future analysis of data taking into account the business nature of the system. The next step is the structural design process. Usually, this process is composed of four steps, including selection of business processes, declaration of granularity, determination of associated dimensions, multidimensional modeling for the construction project data warehouse.

The available data source is operational database which contains contractual data, budgeting, work progress, material cost, labor cost, tools, sub-contractor and general cost.

Based on the available data and business process requirements than the structure of data warehouse designed as star schema in Figure 1, along with its cube dimension in Figure 2.

Figure 1. Data warehouse diagram

Figure 2. Cube Dimension

3.2 Development of business intelligence for construction project cost analysis

The proposed module for project cost analysis include five supporting module: ETL, Project Status, Cost Summary/ Drilldown, Cost & Time Estimation for Completion, S-Curve Schedule Vs Actual progres.

Table 1. Summary of the dashboard and reports provided by the module.

No	List of dashboard	Descriptions
1.	ETL	Extract data from SAKKU, transform and load it to Data Warehouse
2.	Project Status	Status of cost and schedule of project, at current, on schedule, on budget or other conditions, dashboard only
3.	Project Cost	Summary and detail / drill down of actual cost, dashboard and printable report
4.	Prediction	Estimated cost and time for completion of project, dashboard and printable report
5.	S-Curve	Plot S-Curve of schedule and actual progres, dashboard and printable report

Figure 3-5 highlight the interface of the system which indicates the project status, project costs, prediction of time and cost and scheduling.

Figure 3. Project Status

Figure 4. Project Cost

Figure 5. Cost & Time Prediction

Based on observations and interviews related to the reporting process for evaluation at HMP KSO, process and time required of preparing an evaluation report is as follows:

Table 5. Time frame for project evaluation without using BI application:

No.	Description	Time	Note
1.	Time required for completing account transaction, input operational data and data source after cut-off period.	6 days	
2.	Preparing evaluation data (Cost Summary, Cost Detail,	4 days	Overtime until 12PM,

	S-Curve Schedule vs Actual Progres)		when preparing report
3.	Estimate cost and time for completion of project.		(7 days) prepared only after progres>60 %
4.	Sending data to division.	1 day	
5.	Data evaluation at division	1 day	
	Total	12 days	

Based on existing process the time required to prepare data analysis every month can be described as follows:

- Time for preparation manual report + Time for sending and data process at division = 6 days. Using BI application, time required = time for ETL process and printing report in BI application, from the above figure= 14.31 minutes (time for ETL process to host server) = $14.31/60 = 0.2385$ hours. Efficiency given = $(6 \text{ days} - 0.2385 \text{ jam})/6 \text{ days} = (6 \times 8 - 0.2385)/6 \times 8 = 47.7615/48 \times 100\% = 99.50 \%$.
- Efficiency in using resources, because does not need overtime to prepare report.
- Prediction of cost and time for completion can be printed every month.

4. Conclusions

- The design of BI applications at KSO HMP produce information to measure company performance or Key Performance Indicator (KPI), by displaying the Dashboard of Actual Cost, S-Curve Comparison of plan and actual, and Prediction of cost and time completion of the project, which is useful for decision support for executives of KSO HMP, to control costs and completion time.
- Implementation of BI application model, which is accessing data warehouse online provides information analysis quickly, accurately, efficiently and with a visual display make it easier to read the results of the data analysis. BI applications provide acceleration in preparing report evaluation 99.50% compared with the manual reporting process.

REFERENCES

- A. Memon, I. Rahman, M. Abdullah and A. Aziz, "Factors affecting construction cost in MARA large constuctions projects," *Perspective of project management consultant Int.J Sustain. Constr. Eng. Technol*, vol. 1, pp. 41-54, 2010.
- Y. Olawale and M. Sun, "Cost and Time Control of construction projects: Inhibiting factors and mitigating measures in practice," *Cons. Manage. Econ*, no. 28, pp. 509-526, 2010.
- KPMG International, "Global construction survey 2015," March 2015. [Online]. Available: <http://www.kpmg.com/building>.
- Y. Frimpong, J. Oluwoye and L. Crawford, "Causes of delay and cost overruns in construction of groundwater projects in a developing countries, Ghana as a case study," *Int. J. Project Manage*, no. 21, pp. 321-326, 2003.
- F. Fahirah, "Identifikasi Penyebab Overrun Biaya Proyek Konstruksi Gedung," *SmartTek*, vol. 3, no. 3, pp. 160-168, 2005.
- D. Ramdani, "Analisis Faktor Penyebab Pembengkakan Biaya (Cost Overruns) Pada Proyek Konstruksi," 03 May 2013. [Online]. Available: <http://e-journal.uaaj.ac.id/id/eprint/295>. [Accessed 20 04 2015].
- R. Chidambaram and N. S. Potty, "Qualitative analysis of Time delay and Cost Overrun in Multiple Design and Build Projects," in *Civil and Mechanical Engineering*, Denpasar, 2014.
- A. Devlin B and T. Murphy P, "An architecture for a business and information system," *IBM System Jurnal*, pp. 60-80, 1988.
- W. H. Inmon, *Building the Data Warehouse*, Canada: Wiley, 2002.
- F. Codd E, B. Codd S and T. Salley C, "Providing OLAP to User-Analysts: An IT Mandate," *E.F. Codd Associates*, pp. 1-24, 1993.

- [11] K. Chau, Y. Cao, M. Anson and J. Zhang,
"Application of data warehouse and Decision
Support System in construction management,"
Elsevier, Automation in Construction, pp. 213-
224, 2002.
- [12] I. Ahmad, A. Salman and L. Pranas,
"Development of a decision support system
using data warehousing to assist
builders/developers in site selection,"
ELESEVIER - Automation in Construction, pp.
525-542, 2004.
- [13] T. Rujiranyong and J. J. Shi, "A project-
oriented data warehouse for construction,"
Elsevier, Automation in Construction, pp. 800-
807, 2005.
- [14] G. Radivojevic, B. Lazic and G. Sormaz,
"EFFECTS OF BUSINESS INTELLIGENCE
APPLICATION IN TOLLING SYSTEM,"
*International Journal for Traffic and Transport
Engineering*, pp. 45-53, 2014.
- [15] Z. D. Sebestyen and G. D. Babos,
"FORECASTING IN PROJECT
MONITORING SYSTEM BASED ON THE
CONCEPT OF EARNED SCEDULE,"
Management International Conference, pp.
863-876, 2012.